



JEFFERSON COUNTY DRAINAGE DISTRICT NO. 6
Karen J. Stewart, MBA, CTCD/CTCM, Chief Business Officer

6550 Walden Rd., Beaumont, Texas 77707 Phone: 409-842-1818 Fax: 409-842-2729

IFB Number: IFB 22-029/KJS

IFB Title: Re-Bid Relocation of Water and Sanitary Sewer Utilities for the McLean St. Project.

IFB Originally Due: 2:00 PM, CST, Thursday, December 15, 2022

Addendum No.: 1

Issued (Date): December 12, 2022

TO BIDDER: This Addendum is an integral part of the IFB package under consideration by you as a bidding firm in connection with the subject matter herein identified. Jefferson County Drainage District No. 6 deems all sealed bids to have been proffered in recognition and consideration of the entire IFB package – including all addenda. For purposes of clarification, receipt of this present Addendum by a proposing firm should be evidenced by returning it (signed) as part of the proposing firm's sealed response. If the firm's sealed response has already been received by the Jefferson County Drainage District No 6 Purchasing Department, Proposer should return this addendum in a separate sealed envelope, clearly marked with the IFB Name, IFB Number. The information included herein is hereby incorporated into the documents of this present IFB matter and supersedes any conflicting documents or portion thereof previously issued.

Reason for Issuance of this addendum: address Contractor questions.

- 1) **Question:** Will the Contractor be allowed to open-trench install the water and sewer lines or must they be installed via boring?
Answer: The Contractor is allowed to sawcut and open-trench to install the water and sewer lines under the driveways and roads.
- 2) **Question:** Will items 2, 3, and 4 be paid by plan quantity?
Answer: Yes.

***See revised Bid Form**

All addendums will be posted on the DD6 website at <https://dd6.org/departments/purchasing/notices-for-bid/>

Receipt of this Addendum is hereby acknowledged by the undersigned Bidder:

ATTEST:

Witness

Witness

Authorized Signature (Bidder)

Title of Person Signing Above

Typed Name of Business or Individual

Signature

Bid Form

Re-Bid Relocation of Water and Sanitary Sewer Utilities for the McLean St. Project

Item No.	Description	Unit	Estimated Quantity	Unit Cost	Total Cost
1	Preparing Right of Way (Not to exceed \$300 per station)	STA	51		
*2	Excavation (Sewer Utility) (<10 FT.)	C.Y.	2,244		
*3	Excavation (Water Utility) (<8 FT.)	C.Y.	1,041		
*4	Cem Stab Bkfl (1.5 Sk/CY Sand) for Structures & Pipe (Water & Sewer)	C.Y.	875		
5	Mobilization (Not to exceed 10% of the total construction items amount)	L.S.	1		
6	Barricades, Signs, and Traffic Handling	Month	6		
7	Install 8" Sanitary Sewer Lines, Utilizing 8-inch PVC SDR-26, Complete in Place. (Open Trench)	L.F.	130		
8	Install 10" Sanitary Sewer Lines, Utilizing 10-inch PVC SDR-26, Complete in Place. (Open Trench)	L.F.	1,110		
9	Install 4" Sanitary Sewer Lines, Utilizing 4-inch PVC SDR-26, Complete in Place. (Open Trench)	L.F.	50		
10	Install 12" Sanitary Sewer Lines, Utilizing 12-inch PVC SDR-26, Complete in Place. (Open Trench)	L.F.	91		
11	Manholes - Install Fiberglass Manholes (<10 FT.), Complete in Place, all in strict accordance with plans and City of Beaumont Specifications. To include Frame, Grates, Rings and Covers.	Ea.	6		
12	Manholes - Remove & Replace Exist. Sanitary Sewer Structures w/Fiberglass Manholes (<10 FT.), Complete in Place, all in strict accordance with plans and City of Beaumont Specifications. To include Frame, Grates, Rings and Covers.	Ea.	3		
13	Tree Removal (24" Diameter)	Ea.	4		
14	Brush Removal	Ea.	1		
15	Install 6" MJ with 45-degree bend w/Thrust Blocking, Complete in Place.	Ea.	29		
16	Install 6"x6" MJ Cross, Complete in Place.	Ea.	3		
17	Install 6"x6" MJ Tee, Complete in Place.	Ea.	2		
18	Install 6" Adapter, Prop. 6" Watermain to Exist. 6" Watermain (Various Material Type), Complete in Place.	Ea.	11		
19	Install Fire Hydrant Assembly, To Include Valves, Tie-In & Thrust Blocking Complete in Place.	Ea.	2		
20	Remove & Salvage Existing Fire Hydrant Assembly, Complete in Place.	Ea.	2		
21	Install 6" vc class 150-C-900 PVC waterline, Complete in Place.	L.F.	1,680		
22	Install 6" Resilient Wedge Gate Valve & Valve Box as per Sections 805 and 811 of the specifications, Complete in Place.	Ea.	17		

23	Install 1" HDPE PE3408 SDR-9, 200 psi short side service connections, all in strict accordance with plans and City of Beaumont Specifications. (Water)	Ea.	4		
24	Install 1" HDPE PE3408 SDR-9, 200 psi long side service connections, all in strict accordance with plans and City of Beaumont Specifications. (Water)	Ea.	28		
25	Replacement of 4" short side service connection up to property line, w/4" PVC Schedule 40 pipe, complete in place, all in strict accordance with plans and City of Beaumont Specifications. (Sewer)	Ea.	1		
26	Replacement of 4" long side service connection up to property line, w/4" PVC Schedule 40 pipe, complete in place, all in strict accordance with plans and City of Beaumont Specifications. (Sewer)	Ea.	1		
27	Abandonment of Sewers (Section 02222 - City of Houston)	Ea.	3		

Acknowledgment of Addenda (if any):

Addendum 1 _____ Date Received_____

Addendum 2 _____ Date Received_____

Addendum 3 _____ Date Received_____

***Note Items 2, 3, and 4 will be paid by plan quantity**

Bidder Shall Return Completed Form with Offer